6B.3.1 - 13

## GENERAL REQUIREMENTS FACILITY & MAINTENANCE REQUIREMENTS

## BALA

## NORTHEAST METROPOLITAN REGIONAL VOCATIONAL SCHOOL

## FACILITY AND MAINTENANCE REQUIREMENTS

The Design Team has been aware of the facility and maintenance requirements for the new Northeast Metropolitan Vocational High School throughout the planning and design process. Meetings with the school and districts maintenance staff were held to discuss specific building maintenance needs. The following are the maintenance related items particular to the project

- A. General Custodial Requirements:
  - 1. The design team reviewed proposed floor materials, custodial office, closet, and storage locations with persons responsible for maintenance.
- B. Training Hours and Scheduling:
  - MSBA Project Advisory 65 Training Programs for School Construction Projects

     Best Practice guidelines were reviewed with the persons responsible for maintenance.
  - 2. The persons responsible for maintenance agreed that the training schedule and hours and method of delivery will be coordinated toward the end of the construction document phase.
  - 3. Additional reviews with the school and persons responsible for maintenance will be scheduled during the Construction Documents phase.
- C. HVAC Systems
  - 1. The building HVAC systems are proposed to be high efficiency all electric systems to reduce the building greenhouse gas emissions. Refer to HVAC and Electrical narratives for equipment requiring maintenance.
- D. Building Management Systems
  - 1. The building management system is proposed to be a direct digital control system. Refer to the HVAC and Electrical narratives for descriptions.
  - 2. The persons responsible for maintenance were informed that the ATC subcontractor will provide pre-occupancy and post-occupancy training.



- E. Roof Access
  - 1. Rooftop mechanical equipment requiring access by service technicians are located on five (5) different roof areas. Access to each area is per the following:
    - a) Gymnasium Roof: Access is from roof ladders that originate from either the Auditorium Roof or the 3<sup>rd</sup> Floor courtyard roof.
    - b) Auditorium Roof: Access is direct from the 3<sup>rd</sup> floor mechanical room through a man door.
    - c) Main Academic Roof: Can be Accessed either from a roof ladder that originates at the gymnasium roof level or a roof hatch (w/ ladder) located in a fourth-floor storage closet.
    - d) Cafeteria Roof: Accessed directly from a 2<sup>nd</sup> floor mechanical room through a man door.
    - e) Early Education Roof: Accessed through a roof hatch (w/ ladder) located within a first-floor storage closet.
- F. Mechanical Room Access
  - 1. Mechanical rooms are provided access that meets or exceeds the requirements of IMC 2018 Section 306 Access and Service Space.

P:\60-20-409\ADMIN - Northeast Metro Tech\REPORTS-NARRATIVES\2023.01.13\_60%CD Facility Maintenance Narrative\NE Metro Tech 60%CD Facility and Maintenance Narrative.docx