

GENERAL REQUIREMENTS

## LIFE CYCLE COST ANALYSIS – ENERGY & WATER

## Northeast Metropolitan Regional Vocational High School Life-Cycle Cost Estimate Executive Summary

---

Included herein is a life cycle cost estimate for the proposed new Northeast Metropolitan Regional Vocational High School in accordance with the requirements of MGL Chapter 149 Section 44M and per MSBA design development guidelines. This estimate is provided for the HVAC and Plumbing systems.

### STUDY INPUTS

- It is assumed that the District's initial cost will be paid in the form of a municipal bond over a period of 30 years. The interest rate used to determine annual payments is based on 3.5% for the initial municipal bond and 3.5% for the future partial system replacement. The actual rates may differ.
- The study length is based on 30 years, which is consistent with the finance period.
- The discount rate for the cost of money is set at 3.5%.
- The cost for a partial system replacement in year 20 is based on 20% of the initial system cost.
- The initial cost to the district for the HVAC and Plumbing systems is \$17,488,178 after 50% MSBA reimbursement based on cost estimates. This cost is included in the overall bond financing for the project. This study does not include the total finance costs for the overall construction, only the HVAC and Plumbing portion.
- The estimated annual energy cost is \$579,000 (\$1.50 per SF) for the total electric utility cost including energy offsets from the projected electricity production from the utility company provide photovoltaic array. Actual costs may vary based on actual utility rates, building use, operation and climatic factors. An escalation rate of 3.5% is applied annually.
- Estimated annual maintenance costs are based on an estimated cost for an annual service contract by a local maintenance and service provider. Costs are based on \$118,087 (\$0.30 per SF) with a 3.25% annual escalation rate. Actual cost will depend on a final negotiated annual maintenance and service contract with a third party following the completion of construction.
- Salaries for maintenance and operations, supplies, or residual values have not been included.

### STUDY RESULTS

- Cash flow details for principal and interest are provided based on equal payments. These payments are included in the general construction loan.
- The actual total life-cycle cash flow value for the 30-year period is \$73,913,889 with a total present worth life cycle cost of \$41,786,784.
- The portion of the life cycle cost related only to operating cost is \$36,977,015 with a present worth value of \$20,783,021 over the 30-year period.

Prepared by:  
Bala Consulting Engineers

Sean P. Sullivan, P.E.  
Associate, Senior Mechanical Engineer

# Lifecycle Summary


Project: NEMT 90%CD  
Prepared By: BALA

05/12/2023

## NE Metro High School- LCCE for HVAC and Plumbing

30 year life-cycle cost estimate for HVAC system finance and operating costs.

Type of Analysis ..... Public Sector Lifecycle Analysis  
Type of Design Alternatives ..... Independent  
Length of Analysis ..... 30 yrs  
Discount Rate ..... 3.50 %



**Table 1. Executive Summary**

| Economic Criteria            | Best Design Case for Each Criteria             | Value (\$)   |
|------------------------------|------------------------------------------------|--------------|
| Lowest Total Present Worth   | Life Cycle Cost Estimate for HVAC and Plumbing | \$41,786,784 |
| Lowest Annual Operating Cost | Life Cycle Cost Estimate for HVAC and Plumbing | \$697,087    |
| Lowest First Cost            | Life Cycle Cost Estimate for HVAC and Plumbing | \$17,488,178 |

**Table 2. Design Cases Ranked by Total Present Worth**

| Design Case Name                               | Design Case Short Name | Total Present Worth (\$) | Annual Operating Cost (\$/yr) | First Cost (\$) |
|------------------------------------------------|------------------------|--------------------------|-------------------------------|-----------------|
| Life Cycle Cost Estimate for HVAC and Plumbing |                        | \$41,786,784             | \$697,087                     | \$17,488,178    |

## Cash Flow Details


Project: NEMT 90%CD  
Prepared By: BALA

05/12/2023

### NE Metro High School- LCCE for HVAC and Plumbing

30 year life-cycle cost estimate for HVAC system finance and operating costs.

Type of Analysis ..... Public Sector Lifecycle Analysis  
Type of Design Alternatives ..... Independent  
Length of Analysis ..... 30 yrs  
Discount Rate ..... 3.50 %



#### 1A. Component Cash Flows [Life Cycle Cost Estimate for HVAC and Plumbing], Actual Value

| Year | Date    | Cash Investment (\$) | Loan Principal (\$) | Loan Interest (\$) | Total Investment Cost (\$) | Annual Operating Cost (\$) | Non-Annual Operating Cost (\$) | Total Operating Cost (\$) | Total Cash Flow (\$) |
|------|---------|----------------------|---------------------|--------------------|----------------------------|----------------------------|--------------------------------|---------------------------|----------------------|
| 0    | Initial | 0                    | 0                   | 0                  | 0                          | 0                          | 0                              | 0                         | 0                    |
| 1    | 2022    | 0                    | 338,769             | 612,086            | 950,856                    | 721,190                    | 0                              | 721,190                   | 1,672,045            |
| 2    | 2023    | 0                    | 350,626             | 600,229            | 950,856                    | 746,127                    | 0                              | 746,127                   | 1,696,982            |
| 3    | 2024    | 0                    | 362,898             | 587,957            | 950,856                    | 771,926                    | 0                              | 771,926                   | 1,722,782            |
| 4    | 2025    | 0                    | 375,600             | 575,256            | 950,856                    | 798,619                    | 0                              | 798,619                   | 1,749,474            |
| 5    | 2026    | 0                    | 388,746             | 562,110            | 950,856                    | 826,235                    | 0                              | 826,235                   | 1,777,091            |
| 6    | 2027    | 0                    | 402,352             | 548,504            | 950,856                    | 854,807                    | 0                              | 854,807                   | 1,805,662            |

## Cash Flow Details

Project: NEMT 90%CD  
Prepared By: BALA

05/12/2023

| Year   | Date | Cash Investment (\$) | Loan Principal (\$) | Loan Interest (\$) | Total Investment Cost (\$) | Annual Operating Cost (\$) | Non-Annual Operating Cost (\$) | Total Operating Cost (\$) | Total Cash Flow (\$) |
|--------|------|----------------------|---------------------|--------------------|----------------------------|----------------------------|--------------------------------|---------------------------|----------------------|
| 7      | 2028 | 0                    | 416,434             | 534,422            | 950,856                    | 884,367                    | 0                              | 884,367                   | 1,835,223            |
| 8      | 2029 | 0                    | 431,009             | 519,846            | 950,856                    | 914,951                    | 0                              | 914,951                   | 1,865,806            |
| 9      | 2030 | 0                    | 446,094             | 504,761            | 950,856                    | 946,593                    | 0                              | 946,593                   | 1,897,448            |
| 10     | 2031 | 0                    | 461,708             | 489,148            | 950,856                    | 979,330                    | 0                              | 979,330                   | 1,930,186            |
| 11     | 2032 | 0                    | 477,868             | 472,988            | 950,856                    | 1,013,200                  | 0                              | 1,013,200                 | 1,964,056            |
| 12     | 2033 | 0                    | 494,593             | 456,263            | 950,856                    | 1,048,242                  | 0                              | 1,048,242                 | 1,999,098            |
| 13     | 2034 | 0                    | 511,904             | 438,952            | 950,856                    | 1,084,498                  | 0                              | 1,084,498                 | 2,035,353            |
| 14     | 2035 | 0                    | 529,820             | 421,035            | 950,856                    | 1,122,008                  | 0                              | 1,122,008                 | 2,072,863            |
| 15     | 2036 | 0                    | 548,364             | 402,492            | 950,856                    | 1,160,816                  | 0                              | 1,160,816                 | 2,111,671            |
| 16     | 2037 | 0                    | 567,557             | 383,299            | 950,856                    | 1,200,967                  | 0                              | 1,200,967                 | 2,151,823            |
| 17     | 2038 | 0                    | 587,421             | 363,434            | 950,856                    | 1,242,509                  | 0                              | 1,242,509                 | 2,193,364            |
| 18     | 2039 | 0                    | 607,981             | 342,875            | 950,856                    | 1,285,488                  | 0                              | 1,285,488                 | 2,236,344            |
| 19     | 2040 | 0                    | 629,260             | 321,595            | 950,856                    | 1,329,955                  | 0                              | 1,329,955                 | 2,280,811            |
| 20     | 2041 | 0                    | 651,284             | 299,571            | 950,856                    | 1,375,962                  | 0                              | 1,375,962                 | 2,326,817            |
| 21     | 2042 | 0                    | 1,270,366           | 521,611            | 1,791,976                  | 1,423,561                  | 0                              | 1,423,561                 | 3,215,537            |
| 22     | 2043 | 0                    | 1,314,829           | 477,148            | 1,791,976                  | 1,472,807                  | 0                              | 1,472,807                 | 3,264,784            |
| 23     | 2044 | 0                    | 1,360,848           | 431,129            | 1,791,976                  | 1,523,759                  | 0                              | 1,523,759                 | 3,315,735            |
| 24     | 2045 | 0                    | 1,408,477           | 383,499            | 1,791,976                  | 1,576,474                  | 0                              | 1,576,474                 | 3,368,451            |
| 25     | 2046 | 0                    | 1,457,774           | 334,202            | 1,791,976                  | 1,631,015                  | 0                              | 1,631,015                 | 3,422,991            |
| 26     | 2047 | 0                    | 1,508,796           | 283,180            | 1,791,976                  | 1,687,444                  | 0                              | 1,687,444                 | 3,479,420            |
| 27     | 2048 | 0                    | 1,561,604           | 230,373            | 1,791,976                  | 1,745,826                  | 0                              | 1,745,826                 | 3,537,803            |
| 28     | 2049 | 0                    | 1,616,260           | 175,716            | 1,791,976                  | 1,806,230                  | 0                              | 1,806,230                 | 3,598,206            |
| 29     | 2050 | 0                    | 1,672,829           | 119,147            | 1,791,976                  | 1,868,725                  | 0                              | 1,868,725                 | 3,660,702            |
| 30     | 2051 | 0                    | 1,731,378           | 60,598             | 1,791,976                  | 1,933,384                  | 0                              | 1,933,384                 | 3,725,361            |
| Totals |      | 0                    | 24,483,449          | 12,453,426         | 36,936,880                 | 36,977,015                 | 0                              | 36,977,015                | 73,913,889           |

### 1B. Present Worth Cash Flows [Life Cycle Cost Estimate for HVAC and Plumbing]

| Year | Date    | Total Investment Cost (\$) | Total Operating Cost (\$) | Total Present Worth (\$) |
|------|---------|----------------------------|---------------------------|--------------------------|
| 0    | Initial | 0                          | 0                         | 0                        |
| 1    | 2022    | 918,701                    | 696,802                   | 1,615,503                |
| 2    | 2023    | 887,634                    | 696,517                   | 1,584,151                |
| 3    | 2024    | 857,617                    | 696,233                   | 1,553,851                |
| 4    | 2025    | 828,616                    | 695,950                   | 1,524,566                |
| 5    | 2026    | 800,595                    | 695,668                   | 1,496,263                |
| 6    | 2027    | 773,522                    | 695,386                   | 1,468,907                |
| 7    | 2028    | 747,364                    | 695,105                   | 1,442,469                |

## Cash Flow Details

Project: NEMT 90%CD  
Prepared By: BALA

05/12/2023

| Year   | Date | Total Investment Cost<br>(\$) | Total Operating Cost<br>(\$) | Total Present Worth<br>(\$) |
|--------|------|-------------------------------|------------------------------|-----------------------------|
| 8      | 2029 | 722,091                       | 694,824                      | 1,416,915                   |
| 9      | 2030 | 697,672                       | 694,545                      | 1,392,217                   |
| 10     | 2031 | 674,079                       | 694,265                      | 1,368,345                   |
| 11     | 2032 | 651,284                       | 693,987                      | 1,345,271                   |
| 12     | 2033 | 629,260                       | 693,709                      | 1,322,970                   |
| 13     | 2034 | 607,981                       | 693,432                      | 1,301,413                   |
| 14     | 2035 | 587,421                       | 693,156                      | 1,280,577                   |
| 15     | 2036 | 567,557                       | 692,880                      | 1,260,437                   |
| 16     | 2037 | 548,364                       | 692,605                      | 1,240,969                   |
| 17     | 2038 | 529,820                       | 692,331                      | 1,222,151                   |
| 18     | 2039 | 511,904                       | 692,057                      | 1,203,961                   |
| 19     | 2040 | 494,593                       | 691,784                      | 1,186,377                   |
| 20     | 2041 | 477,868                       | 691,511                      | 1,169,379                   |
| 21     | 2042 | 870,132                       | 691,240                      | 1,561,371                   |
| 22     | 2043 | 840,707                       | 690,968                      | 1,531,675                   |
| 23     | 2044 | 812,277                       | 690,698                      | 1,502,975                   |
| 24     | 2045 | 784,809                       | 690,428                      | 1,475,237                   |
| 25     | 2046 | 758,269                       | 690,159                      | 1,448,429                   |
| 26     | 2047 | 732,627                       | 689,891                      | 1,422,518                   |
| 27     | 2048 | 707,853                       | 689,623                      | 1,397,475                   |
| 28     | 2049 | 683,916                       | 689,355                      | 1,373,271                   |
| 29     | 2050 | 660,788                       | 689,089                      | 1,349,877                   |
| 30     | 2051 | 638,443                       | 688,823                      | 1,327,266                   |
| Totals |      | 21,003,764                    | 20,783,021                   | 41,786,786                  |

## Design Case Inputs

Project: NEMT 90%CD

05/12/2023

Prepared By: BALA

Type of Analysis.....Public Sector Lifecycle Analysis  
Length of Analysis.....30 yrs  
Income Taxes ..... Not Considered

### General Information :

Design Case Name ..... Life Cycle Cost Estimate for HVAC and Plumbing

Design Case Short Name ...

Description:

30 year life-cycle cost estimate for HVAC system finance and operating costs.

### Investment Costs :

| Cost Item                         | Cost (\$)    | Year Incurred | Esc Rate (%/yr) | Salvage Value (\$) | Useful Life (yrs) |
|-----------------------------------|--------------|---------------|-----------------|--------------------|-------------------|
| Proposed Mech System Initial Cost | \$ 9,000,000 | 0             | 0.00            | \$ 0               | 30                |
| Proposed Mech System Initial Cost | \$ 8,488,178 | 0             | 0.00            | \$ 0               | 30                |
| Mech System Replacement Cost      | \$ 6,995,271 | 20            | 0.00            | \$ 0               | 10                |

### Loans :

| Loan Item                         | Start Year | Investment In Start Year (\$) | Percent Financed | Term Of Loan (Years) | Interest Rate (%/yr) | Payment Method |
|-----------------------------------|------------|-------------------------------|------------------|----------------------|----------------------|----------------|
| Municipal Bond Financing for HVAC | 0          | \$ 24,483,449                 | 100              | 30                   | 3.50                 | Equal Payments |
| Replacement Cost Financing        | 20         | \$ 24,483,449                 | 100              | 10                   | 3.50                 | Equal Payments |

### Annual Operating Costs :

| Cost Item                | Cost (\$)  | Start Year | Number Of Years | Esc Rate (%/yr) |
|--------------------------|------------|------------|-----------------|-----------------|
| Annual Energy Costs      | \$ 579,000 | 1          | 30              | 3.50            |
| Annual Maintenance Costs | \$ 118,087 | 1          | 30              | 3.25            |

*There are no non-annual operating cost inputs*

## Study Inputs

Project: NEMT 90%CD  
Prepared By: BALA

05/12/2023

Study Title ..... NE Metro High School- LCCE for HVAC and Plumbing

Study Description:

30 year life-cycle cost estimate for HVAC system finance and operating costs.

Type of Analysis ..... Public Sector Lifecycle Analysis

Type of Design Alternatives ..... Independent

Base Year ..... 2022

Currency Symbol ..... \$

Length of Analysis ..... 30 yrs

Discount Rate ..... 3.50 %